

Walls 04FAc



Walls:	04FAc1	04FAc2	04FAc3
Manufactured:	July 2, 1998¹	July 8, 1998¹	July 8, 1998¹
MOE data files:	4fac1s.prn	4fac2s.prn	4iac2s.prn
MOE _{plates} (10 ⁶ psi)			
MOE _{studs} (10 ⁶ psi)	1.68	1.37	1.27
Density _{plates} (kg/m ³)			
Density _{studs} (kg/m ³)	496	441	410
Date tested:	July 28, 1998	July 28, 1998	August 2, 1998
Time tested:	14:18	18:21	13:42
LTC files:	30alexcy	30alexcy	30alex4
Data files:	04FAc1.dat	04FAc2.dat	04FAc3.dat
Excel files:	04FAc1_data 04FAc1_UTP	04FAc2_data 04FAc2_UTP	04FAc3_data 04FAc3_UTP
Photo files:	590-598	599-609	702-717

¹ Sheathing attached with 1/2+1/4-in. edge distance.

Wall 04FAc1

Observations: The wall exhibited extremely ductile performance. It was the weakest in the series: the average peak load was 1.9 Kips (0.48 Kip/ft.). It reached the peak resistance between 1.5 and 2.4-in. amplitudes and then gradually degraded until failure occurred at 3.3-in. amplitude. The uplift and sheathing displacement measurements showed symmetrical response on both sides of the positive and negative envelopes.

Failure mode: Both end studs separated from the top plate. Sheathing unzipped from both end studs and from the bottom plate (Photo 594). Along the bottom plate: 5 sheathing nails failed in fatigue; at the left stud: 50%; at the right stud: nails pulled out of wood. At the corners, nails tend to pull out, while in the mid-span, nails fatigue.

Wall 04FAc2

Observations: The wall exhibited more rigid performance than other walls in this series and in the monotonic test series. The average peak load 2.4 Kips (0.60 Kip/ft.) was 25% higher than that of 04FAc1 wall. Similar to other walls, it reached the peak resistance between 1.8 and 2.4-in. amplitudes. However, it degraded somewhat faster and the 20% load decrease occurred during 3.0-in. phase. Again, the performance was symmetric.

Failure mode: Sheathing unzipped from the left end stud and the bottom plate, at the top-left and bottom-right corners (Photos 603-605). Along the bottom plate: 6 sheathing nails failed in fatigue; at the left stud: 7 nails; at the right stud: 3 nails (at the lower part). Other nails pulled heads through sheathing. Nails in field pulled out partly from wood. At the corners, nails pulled out. Fatigue rupture occurs at about 1 in. from the nail head.

Because of the 25% difference in strength of 04FAc1 and 04FAc2 walls, the third wall was tested.

Wall 04FAc3

Observations: The performance parameters of this wall were between the other walls in this series. The average peak load 2.1 Kips (0.53 Kip/ft.) was reached between 2.1 and 2.4-in. amplitudes. Similar to 04FAc1 wall, it degraded smoothly and the 20% load decrease occurred during 3.3-in. phase. The performance was symmetric with a lot of racking.

Failure mode: The wall exhibited slightly less rigid performance than in monotonic tests 04FAm. Shape of envelope curve is similar to monotonic test 4FAc1; it reached peak load between 1.8 and 2.1-in. displacement and failed at 3-in. amplitude. The sheathing unzipped at the top and bottom plates and along the left end stud. The end studs separated from the top plate (Photo 704, 709). Along the left stud: 3nails failed in fatigue; along the bottom plate: 3 nails failed in fatigue. Seven nails pulled out of wood at the left stud (Photo 711). The nails at the mid-span pulled heads through sheathing, at the corners- tore through the edge (Photos 714-717).

Data acquisition: The data acquisition started late during the second cycle. The load range on the UTP controller was set at 5500 lbf., while the calibration factor in the LTC file was for the 11000 lbf. range. The row load data need to be adjusted by factor 0.5.

General

Load transfer: During the first test, the end of the short distribution beam on casters lifted up from the floor on the positive stroke. This movement applied significant torque to the wall, which might have affected the wall resistance. On the negative stroke, the caster #2 bumped the floor, which created some noise in DAQ of diagonal pots. During the following tests, the short distribution beam was replaced by the long one, which eliminated the uplift problem.

Instrumentation: During 04FAc1 and 04FAc2 tests, Bolt #1 did not produce data (a lead was cut during installation). New tension bolt was installed for 04FAc3 test. Sheathing LVDT's # 1 and #4 were prone to damage when the sheathing unzipped. They need to be taken off after 3-in. amplitude. Also, the diagonal pot wires were removed before the end of the test to avoid their collapse.

Table 04FAc1. Data summary.

Specimen		04FAc1	Per unit length	
Tie-Down Anchors		cyclic test		
Wall length		4.00ft.	1.219m	
Date:	7-28-1998	Time:	14:18	
EEEP Parameters		units	initial	stabilized
Peak unit load, v_{peak}	Kip/ft.	0.481	0.432	
	KN/m	7.025	6.310	
Drift at peak load, Δ_{peak}	in.	1.799	1.812	
	mm	45.69	46.03	
Yield unit load, v_{yield}	Kip/ft.	0.439	0.400	
	KN/m	6.401	5.844	
Drift at yield load, Δ_{yield}	in.	0.342	0.445	
	mm	8.70	11.30	
Proportional limit, $0.4v_{peak}$	Kip/ft.	0.193	0.173	
	KN/m	2.810	2.524	
Drift at prop. limit, $\Delta@0.4v_{peak}$	in.	0.150	0.192	
	mm	3.82	4.88	
Unit load at failure or $0.8v_{peak}$	Kip/ft.	0.385	0.346	
	KN/m	5.620	5.048	
Drift at failure, $\Delta_{failure}$	in.	3.256	3.144	
	mm	82.71	79.85	
Shear modulus, G $@0.4v_{peak}$	Kip/in.	10.291	7.222	
	KN/mm	1.802	1.265	
Work until failure per unit length	Kip-ft./ft.	1.602	1.777	
	KN-m/m	7.126	7.904	
Unit load, $v_{1/300}$ $@ 0.32$ in. (8.13 mm)	Kips/ft.	0.287	0.277	
	KN/m	4.190	4.044	
Unit load, $v_{1/200}$ $@ 0.48$ in.(12.19 mm)	Kips/ft.	0.338	0.319	
	KN/m	4.927	4.651	
Unit load, $v_{1/100}$ $@ 0.96$ in. (24.38 mm)	Kips/ft.	0.442	0.404	
	KN/m	6.446	5.894	
Unit load, $v_{1/60}$ $@ 1.6$ in. (40.64 mm)	Kips/ft.	0.476	0.425	
	KN/m	6.946	6.195	
EVDR $@v_{peak}$			0.137	0.129

SEAOSC parameters		units	negative	positive	average
Yield Limit State	v_{YLS}	Kips/ft.	-0.265	0.296	0.280
		KN/m	-3.871	4.312	4.092
	Δ_{YLS}	in.	-0.302	0.296	0.299
		mm	-7.67	7.52	7.59
Strength Limit State	G'_{YLS}	Kip/in.	7.031	7.989	7.505
		KN/mm	1.231	1.399	1.314
	v_{SLS}	Kips/ft.	-0.475	0.488	0.481
KN/m		-6.935	7.114	7.025	
Δ_{SLS}	in.	-2.426	1.482	1.954	
	mm	-61.62	37.65	49.63	
G'_{SLS}	Kip/in.	1.567	2.631	1.971	
	KN/mm	0.274	0.461	0.345	




Figure 04FAc1- a. Observed load-deflection curve¹.




Figure 04FAc1- b. Envelopes, SEAOSC, and EEEP curves².

¹ The scale of the graph varies between test series.

² The scale of the graph is uniform between test series for comparison purposes.




Figure 04FAc1- c. Vertical displacement of studs (initial envelope).




Figure 04FAc1- d. Sheathing displacement (initial envelope).




Figure 04FAc1- e. Forces in anchor bolts (initial envelope).




Figure 04FAc1- f. Load- and displacement-time record.

Table 04FAc2. Data summary.

Specimen		04FAc2	Per unit length	
Tie-Down Anchors		cyclic test		
Wall length		4.00ft.	1.219m	
Date:	7-28-1998	Time:	18:21	
EEEP Parameters		units	initial	stabilized
Peak unit load, v_{peak}	Kip/ft.	0.599	0.527	
	KN/m	8.734	7.696	
Drift at peak load, Δ_{peak}	in.	1.961	1.803	
	mm	49.82	45.80	
Yield unit load, v_{yield}	Kip/ft.	0.541	0.485	
	KN/m	7.897	7.075	
Drift at yield load, Δ_{yield}	in.	0.461	0.499	
	mm	11.70	12.67	
Proportional limit, $0.4v_{peak}$	Kip/ft.	0.239	0.211	
	KN/m	3.494	3.078	
Drift at prop. limit, $\Delta@0.4v_{peak}$	in.	0.204	0.217	
	mm	5.18	5.51	
Unit load at failure or $0.8v_{peak}$	Kip/ft.	0.479	0.422	
	KN/m	6.987	6.157	
Drift at failure, $\Delta_{failure}$	in.	2.939	2.788	
	mm	74.65	70.81	
Shear modulus, G $@0.4v_{peak}$	Kip/in.	9.401	7.781	
	KN/mm	1.646	1.363	
Work until failure per unit length	Kip-ft./ft.	1.449	1.609	
	KN-m/m	6.446	7.159	
Unit load, $v_{1/300}$ $@ 0.32$ in. (8.13 mm)	Kips/ft.	0.311	0.301	
	KN/m	4.543	4.398	
Unit load, $v_{1/200}$ $@ 0.48$ in.(12.19 mm)	Kips/ft.	0.382	0.363	
	KN/m	5.579	5.302	
Unit load, $v_{1/100}$ $@ 0.96$ in. (24.38 mm)	Kips/ft.	0.525	0.481	
	KN/m	7.655	7.025	
Unit load, $v_{1/60}$ $@ 1.6$ in. (40.64 mm)	Kips/ft.	0.589	0.525	
	KN/m	8.593	7.666	
EVDR $@v_{peak}$			0.125	0.115

SEAOSC parameters		units	negative	positive	average
Yield Limit State	v_{YLS}	Kips/ft.	-0.295	0.312	0.303
		KN/m	-4.301	4.546	4.424
	Δ_{YLS}	in.	-0.305	0.299	0.302
		mm	-7.74	7.59	7.66
Strength Limit State	G'_{YLS}	Kip/in.	7.739	8.340	8.036
		KN/mm	1.355	1.460	1.407
	v_{SLS}	Kips/ft.	-0.591	0.603	0.597
KN/m		-8.632	8.800	8.716	
Δ_{SLS}	in.	-1.814	2.414	2.114	
	mm	-46.06	61.32	53.69	
G'_{SLS}	Kip/in.	2.609	1.998	2.260	
	KN/mm	0.457	0.350	0.396	




Figure 04FAc2- a. Observed load-deflection curve.




Figure 04FAc2- b. Envelopes, SEAOSC, and EEEP curves.




Figure 04FAc2- c. Vertical displacement of studs (initial envelope).




Figure 04FAc2- d. Sheathing displacement (initial envelope).




Figure 04FAc2- e. Forces in anchor bolts (initial envelope).




Figure 04FAc2- f. Load- and displacement-time record.

Table 04FAc3. Data summary.

Specimen		04FAc3	Per unit length	
Tie-Down Anchors		cyclic test		
Wall length		4.00ft.	1.219m	
Date:	8-02-1998	Time:	13:42	
EEEP Parameters		units	initial	stabilized
Peak unit load, v_{peak}	Kip/ft.	0.533	0.472	
	KN/m	7.775	6.888	
Drift at peak load, Δ_{peak}	in.	2.262	1.963	
	mm	57.45	49.86	
Yield unit load, v_{yield}	Kip/ft.	0.483	0.434	
	KN/m	7.047	6.333	
Drift at yield load, Δ_{yield}	in.	0.482	0.500	
	mm	12.25	12.70	
Proportional limit, $0.4v_{peak}$	Kip/ft.	0.213	0.189	
	KN/m	3.110	2.755	
Drift at prop. limit, $\Delta@0.4v_{peak}$	in.	0.213	0.217	
	mm	5.41	5.52	
Unit load at failure or $0.8v_{peak}$	Kip/ft.	0.426	0.378	
	KN/m	6.220	5.510	
Drift at failure, $\Delta_{failure}$	in.	3.227	3.105	
	mm	81.96	78.88	
Shear modulus, G $@0.4v_{peak}$	Kip/in.	8.015	6.947	
	KN/mm	1.404	1.217	
Work until failure per unit length	Kip-ft./ft.	1.710	1.884	
	KN-m/m	7.605	8.380	
Unit load, $v_{1/300}$ $@ 0.32$ in. (8.13 mm)	Kips/ft.	0.276	0.269	
	KN/m	4.022	3.924	
Unit load, $v_{1/200}$ $@ 0.48$ in.(12.19 mm)	Kips/ft.	0.338	0.323	
	KN/m	4.931	4.715	
Unit load, $v_{1/100}$ $@ 0.96$ in. (24.38 mm)	Kips/ft.	0.467	0.427	
	KN/m	6.808	6.232	
Unit load, $v_{1/60}$ $@ 1.6$ in. (40.64 mm)	Kips/ft.	0.522	0.466	
	KN/m	7.620	6.793	
EVDR $@v_{peak}$			0.135	0.127

SEAOSC parameters		units	negative	positive	average
Yield Limit State	v_{YLS}	Kips/ft.	-0.379	0.274	0.326
		KN/m	-5.525	3.997	4.761
	Δ_{YLS}	in.	-0.609	0.299	0.454
		mm	-15.48	7.59	11.53
Strength Limit State	G'_{YLS}	Kip/in.	4.970	7.333	5.748
		KN/mm	0.870	1.284	1.007
	v_{SLS}	Kips/ft.	-0.532	0.534	0.533
		KN/m	-7.760	7.789	7.775
Δ_{SLS}	in.	-2.423	2.101	2.262	
	mm	-61.54	53.36	57.45	
G'_{SLS}	Kip/in.	1.756	2.033	1.884	
	KN/mm	0.307	0.356	0.330	




Figure 04FAc3- a. Observed load-deflection curve.




Figure 04FAc3- b. Envelopes, SEAOSC, and EEEP curves.




Figure 04FAc2- c. Vertical displacement of studs (initial envelope).




Figure 04FAc3- d. Sheathing displacement (initial envelope).




Figure 04FAc3- e. Forces in anchor bolts (initial envelope).




Figure 04FAc3- f. Load- and displacement-time record.