


Walls 04NAm




Wall:	04NAm1	04NAm1r	04NAm1r3
Manufactured:	June 21, 1998	June 21, 1998	June 21, 1998
MOE data files:	4nac1s.prn	4nac1s.prn	4nac1s.prn
MOE _{plates} (10 ⁶ psi)			
MOE _{studs} (10 ⁶ psi)	1.46	1.46	1.46
Density _{plates} (kg/m ³)			
Density _{studs} (kg/m ³)	493	493	493
Date tested:	August 7, 1998 ¹	August 7, 1998 ²	August 7, 1998 ³
Time tested:	12:22	13:47	15:43
LTC files:			
Data files:	04NAm1.dat	04NAm1r.dat	04NAm1r3.dat
Excel files:	04NAm1_data	04NAm1r_data	04NAm1r3_data
Photo files:	791-796	797-800	801-805

¹ The bottom plate was attached to the base with 1 row of 16d nails at 3 in. o. c. one hour before the test.

² The test was conducted on 04NAm1 wall. The bottom plate was attached to the base with 2 rows of 16d nails at 3 in. o. c. one hour before the test. The original bottom plate and base were used.

³ The test was conducted on 04NAm1 wall. The bottom plate was attached to the base with 3 rows of 16d nails at 3 in. o. c. one hour before the test. The original bottom plate and base were used. The sheathing was attached to with 3/8-in. edge distance



Wall:	04NA_m1r4	04NA_m1r5
Manufactured:	June 21, 1998	June 21, 1998
MOE data files:	4nac1s.prn	4nac1s.prn
MOE _{plates} (10 ⁶ psi)		
MOE _{studs} (10 ⁶ psi)	1.46	1.46
Density _{plates} (kg/m ³)		
Density _{studs} (kg/m ³)	493	493
Date tested:	August 10, 1998¹	August 10, 1998²
Time tested:	12:47	13:58
LTC files:	alex_4m	alex_4m
Data files:	04NA _m 14.dat	04NA _m 1r5.dat
Excel files:	04NA _m 14_data	04NA _m 1r5_data
Photo files:	809-811	812-813

¹ The test was conducted on 04NA_m1 wall. The bottom plate was attached to the base with nine nails at each corner (3 rows of 16d nails at 3 in. o. c.) one hour before the test. The new bottom plate and new base were used. The sheathing was attached with 3/4-in. edge distance.

² The test was conducted on 04NA_m1 wall. The bottom plate was attached to the base with 3 rows of 16d nails at 3 in. o. c. half hour before the test. The same bottom plate and the base were used.

General

Rationale: During the tests, there was no dead load applied in the wall plane. Therefore, the wall uplift resistance was provided only by the withdrawal resistance of nails attaching the wall to the base. This situation was similar to real-life practices when the walls parallel to the floor joists carry low gravity loads. During these tests, the required number of nails to prevent the specimen overturning was determined. All five tests were conducted on the same specimen because little or no damage occurred to the wall.

Data processing: During these tests, the load-deflection record was affected by the nail withdrawal. The observed load data was filtered by taking the average of 75 load readings (5 seconds). The summary tables show performance parameters determined from the recorded data (column “observed”) and from the filtered data (column “filtered”). The filter helped estimating the failure point more accurately.

Wall 04NA_m1

Observations: This wall was attached to the base with twelve 16d nails (one row at 3 in. o. c.). Early in the test (0.16 in.), the wall started overturning due to nail withdrawal from the base. The peak resistance was reached at approximately 0.75 in. deflection. The nail withdrawal continued gradually providing the average “yield” resistance of 0.3 Kips/ft. The wall rocked as a rigid body around the left-end corner. Sheathing displacement relative to the framing was negligible with the exception of the right-bottom corner, where the displacement reached 0.04 in.

Failure mode: The nails attaching the wall to the base withdrew (Photos 791, 792,795).

Wall 04NA_m1r

Observations: This wall was attached to the base with twenty-four 16d nails (two rows at 3 in. o. c.). Similar to the first test, the wall started early overturning due to nail withdrawal from the base. The peak resistance was slightly higher and was reached later (at approximately 1.0 in. deflection). The wall rocked as a rigid body around the left-end corner until the nails withdrew from the base. Sheathing displacement relative to the framing was negligible with the exception of the right-bottom corner, where the displacement reached 0.09 in.

Failure mode: The nails attaching the wall to the base withdrew (Photos 797, 798,800).

Data acquisition: The data after 1.5 in. was not recorded.

Wall 04NA_m1r3

Observations: This wall was attached to the base with thirty-six 16d nails (three rows at 3 in. o. c.). The response of this wall was significantly different from the previous tests. The 36 nails provided sufficient resistance to prevent the wall overturning. The peak resistance 628 lbf. (0.16 Kips/ft.) was reached at 1.9 in. deflection. The elastic stiffness was low due to the effect of the previous tests. Note, this wall was tested twice before and the bottom plate was not replaced. Sheathing displacement relative to the framing was negligible with the exception of the bottom plate, which separated from the sheathing similar to 04IA_m walls. The degradation of wall strength was gradual. The 20% resistance reduction was observed at 2.4-in. deflection.

Failure mode: The sheathing separated from the bottom plate (Photos 801, 804). Sheathing nails tore through the sheathing edge. The edge distance was 3/8 in. and less (Photo 803).

Wall 04NA_m1r4

Rationale: The 04NA_m1r3 test showed that 36 nails attaching the specimen to the base were more than adequate to prevent the wall overturning. The 04NA_m1r4 test was designed assuming that the nails closest to the corner contribute the overturning resistance the most. The specimen was attached to the base with nine nails in each corner, 3 rows at 3 in. o. c. (Photo 809). The new base and the bottom plate were applied. The sheathing was attached at 6 in. o. c. with ¾-in. edge distance.

Observations: The initial part of the load-deflection curve was steep. Apparently, the dense placement of nails provided initial overturning resistance. However, early in the test (0.17 in.), the nail withdrawal from the base started influencing the wall response. The peak resistance was reached at 0.86 in. deflection, and then the nails 'gave up'. It can clearly be seen on Figure 04NA_m1r4-d. Initially, the sheathing panel was moving relative to the bottom plate, indicating the work of the sheathing nails. At the critical point (0.86 in.) the separation stopped and the bottom plate started the uplift displacement together with the rest of the wall.

Failure mode: The nails attaching the wall to the base withdrew (Photos 812, 813).

Wall 04NA_m1r5

Observations: This wall was attached to the base with thirty-six 16d nails (three rows at 3 in. o. c.). It was a replication of 04NA_m1r3 test. The sheathing was attached to the bottom plate with ¾-in. edge distance. The response of this wall was stiffer and stronger than in the previous tests and comparable with 04IA_m walls. The peak resistance 747 lbf. (0.19 Kips/ft.) was reached at 1.35 in. deflection. Sheathing displacement relative to the framing was negligible with the exception of the bottom plate, which separated from the sheathing similar to 04IA_m walls. The degradation of wall strength was gradual. The 20% resistance reduction was observed at 2.0-in. deflection.

Failure mode: The sheathing separated from the bottom plate (Photos 812, 813). Sheathing nails tore through the sheathing edge.

Table 04NA_m1. Data summary.

Specimen	04NA _m 1	Per unit length		
Nails		monotonic test		
Wall length		4.00ft.	1.219m	
Date:	8-07-1998.	Time:	12:22	
		units	observed	filtered
Peak unit load, v_{peak}		Kip/ft.	0.101	0.092
		KN/m	1.481	1.339
Drift at peak load, Δ_{peak}		in.	1.254	1.249
		mm	31.85	31.73
Yield unit load, v_{yield}		Kip/ft.	0.081	0.083
		KN/m	1.183	1.209
Drift at yield load, Δ_{yield}		in.	0.235	0.232
		mm	5.98	5.89
Proportional limit, $0.4v_{\text{peak}}$		Kip/ft.	0.041	0.037
		KN/m	0.592	0.536
Drift at prop. limit, $\Delta@0.4v_{\text{peak}}$		in.	0.118	0.103
		mm	2.99	2.61
Unit load at failure or $0.8v_{\text{peak}}$		Kip/ft.	0.080	0.073
		KN/m	1.167	1.061
Drift at failure, Δ_{failure}		in.	1.304	2.968
		mm	33.11	75.38
Shear modulus, G @ $0.4v_{\text{peak}}$		Kip/in.	2.755	2.857
		KN/mm	0.483	0.500
Work until failure per unit length		Kip-ft./ft.	0.008	0.020
		KN·m/m	0.036	0.088
Unit load, $v_{1/300}$ @ 0.32 in. (8.13 mm)		Kips/ft.	0.062	0.060
		KN/m	0.901	0.879
Unit load, $v_{1/200}$ @ 0.48 in. (12.19 mm)		Kips/ft.	0.069	0.071
		KN/m	1.000	1.032
Unit load, $v_{1/100}$ @ 0.96 in. (24.38 mm)		Kips/ft.	0.087	0.090
		KN/m	1.263	1.307
Unit load, $v_{1/60}$ @ 1.6 in. (40.64 mm)		Kips/ft.	0.090	0.091
		KN/m	1.314	1.334




Figure 04NA m 1- a. Observed and filtered load-deflection curves¹.




Figure 04NA m 1- b. Unit load-deflection and EEEP curves².

¹ The scale of the graph varies between test series.

² The scale of the graph is uniform between test series for comparison purposes.




Figure 04NA_m1- c. Vertical displacement of studs.




Figure 04NA_m1- d. Sheathing displacement.

Table 04NAm1r. Data summary.

Specimen	04NAm1r	Per unit length		
Nails		monotonic test		
Wall length		4.00ft.	1.219m	
Date:	8-07-1998.	Time:	13:47	
		units	observed	filtered
Peak unit load, v_{peak}		Kip/ft.	0.132	0.122
		KN/m	1.919	1.773
Drift at peak load, Δ_{peak}		in.	1.436	1.354
		mm	36.46	34.38
Yield unit load, v_{yield}		Kip/ft.	0.105	0.102
		KN/m	1.529	1.495
Drift at yield load, Δ_{yield}		in.	0.382	0.346
		mm	9.71	8.79
Proportional limit, $0.4v_{peak}$		Kip/ft.	0.053	0.049
		KN/m	0.768	0.709
Drift at prop. limit, $\Delta@0.4v_{peak}$		in.	0.192	0.164
		mm	4.87	4.17
Unit load at failure or $0.8v_{peak}$		Kip/ft.	0.123	0.119
		KN/m	1.791	1.733
Drift at failure, $\Delta_{failure}$		in.	1.500	1.449
		mm	38.10	36.81
Shear modulus, G @ $0.4v_{peak}$		Kip/in.	2.194	2.368
		KN/mm	0.384	0.415
Work until failure per unit length		Kip-ft./ft.	0.011	0.011
		KN·m/m	0.051	0.048
Unit load, $v_{1/300}$ @ 0.32 in. (8.13 mm)		Kips/ft.	0.062	0.062
		KN/m	0.901	0.902
Unit load, $v_{1/200}$ @ 0.48 in.(12.19 mm)		Kips/ft.	0.081	0.076
		KN/m	1.175	1.115
Unit load, $v_{1/100}$ @ 0.96 in. (24.38 mm)		Kips/ft.	0.115	0.109
		KN/m	1.675	1.591
Unit load, $v_{1/60}$ @ 1.6 in. (40.64 mm)		Kips/ft.	N/A	N/A
		KN/m	N/A	N/A




Figure 04NA_m1r- a. Observed and filtered load-deflection curves.




Figure 04NA_m1r- b. Unit load-deflection and EEEP curves.




Figure 04NA_m1r- c. Vertical displacement of studs.




Figure 04NA_m1r- d. Sheathing displacement.

Table 04NAm1r4. Data summary.

Specimen	04NAm1r4	Per unit length		
Nails		monotonic test		
Wall length		4.00ft.	1.219m	
Date:	8-10-1998.	Time:	12:47	
		units	observed	filtered
Peak unit load, v_{peak}		Kip/ft.	0.137	0.127
		KN/m	1.999	1.852
Drift at peak load, Δ_{peak}		in.	0.820	0.761
		mm	20.84	19.34
Yield unit load, v_{yield}		Kip/ft.	0.112	0.112
		KN/m	1.636	1.629
Drift at yield load, Δ_{yield}		in.	0.138	0.140
		mm	3.50	3.56
Proportional limit, $0.4v_{peak}$		Kip/ft.	0.055	0.051
		KN/m	0.800	0.741
Drift at prop. limit, $\Delta@0.4v_{peak}$		in.	0.067	0.064
		mm	1.71	1.62
Unit load at failure or $0.8v_{peak}$		Kip/ft.	0.097	0.099
		KN/m	1.412	1.442
Drift at failure, $\Delta_{failure}$		in.	0.823	2.038
		mm	20.91	51.76
Shear modulus, G @ $0.4v_{peak}$		Kip/in.	6.504	6.380
		KN/mm	1.139	1.117
Work until failure per unit length		Kip-ft./ft.	0.007	0.018
		KN·m/m	0.031	0.081
Unit load, $v_{1/300}$ @ 0.32 in. (8.13 mm)		Kips/ft.	0.108	0.105
		KN/m	1.576	1.534
Unit load, $v_{1/200}$ @ 0.48 in. (12.19 mm)		Kips/ft.	0.112	0.117
		KN/m	1.627	1.705
Unit load, $v_{1/100}$ @ 0.96 in. (24.38 mm)		Kips/ft.	0.112	0.119
		KN/m	1.635	1.734
Unit load, $v_{1/60}$ @ 1.6 in. (40.64 mm)		Kips/ft.	0.124	0.111
		KN/m	1.803	1.613




Figure 04NA m 1r4- a. Observed and filtered load-deflection curves.




Figure 04NA m 1r4- b. Unit load-deflection and EEEP curves.




Figure 04NA_m1r4- c. Vertical displacement of studs.




Figure 04NA_m1r4- d. Sheathing displacement.

Table 04NA_m1r3. Data summary.

Specimen	04IA _m 1r3	Per unit length	
Nails		monotonic test	
Wall length		4.00ft.	1.219m
Date:	7-07-1998.	Time:	15:43
		units	04IA _m 1r3
Peak unit load, v_{peak}		Kip/ft. KN/m	0.157 2.291
Drift at peak load, Δ_{peak}		in. mm	1.878 47.70
Yield unit load, v_{yield}		Kip/ft. KN/m	0.133 1.938
Drift at yield load, Δ_{yield}		in. mm	0.545 13.84
Proportional limit, $0.4v_{\text{peak}}$		Kip/ft. KN/m	0.063 0.916
Drift at prop. limit, $\Delta@0.4v_{\text{peak}}$		in. mm	0.258 6.55
Unit load at failure or $0.8v_{\text{peak}}$		Kip/ft. KN/m	0.125 1.831
Drift at failure, Δ_{failure}		in. mm	2.443 62.06
Shear modulus, G $@0.4v_{\text{peak}}$		Kip/in. KN/mm	1.949 0.341
Work until failure per unit length		Kip-ft./ft. KN-m/m	0.024 0.107
Unit load, $v_{1/300}$ $@ 0.32 \text{ in. (8.13 mm)}$		Kips/ft. KN/m	0.066 0.960
Unit load, $v_{1/200}$ $@ 0.48 \text{ in. (12.19 mm)}$		Kips/ft. KN/m	0.075 1.098
Unit load, $v_{1/100}$ $@ 0.96 \text{ in. (24.38 mm)}$		Kips/ft. KN/m	0.122 1.784
Unit load, $v_{1/60}$ $@ 1.6 \text{ in. (40.64 mm)}$		Kips/ft. KN/m	0.151 2.204




Figure 04NAm1r3- a. Observed load-deflection curve.




Figure 04NAm1r3- b. Unit load-deflection and EEEP curves.




Figure 04NA_m1r3- c. Vertical displacement of studs.




Figure 04NA_m1r3- d. Sheathing displacement.

Table 04NA_m1r5. Data summary.

Specimen	04NA _m 1r5	Per unit length		
Nails		monotonic test		
Wall length		4.00ft.	1.219m	
Date:	8-10-1998.	Time:	13:58	
		units	observed	filtered
Peak unit load, v_{peak}		Kip/ft.	0.187	0.180
		KN/m	2.725	2.633
Drift at peak load, Δ_{peak}		in.	1.356	1.346
		mm	34.45	34.20
Yield unit load, v_{yield}		Kip/ft.	0.165	0.162
		KN/m	2.411	2.367
Drift at yield load, Δ_{yield}		in.	0.403	0.399
		mm	10.25	10.13
Proportional limit, $0.4v_{peak}$		Kip/ft.	0.075	0.072
		KN/m	1.090	1.053
Drift at prop. limit, $\Delta@0.4v_{peak}$		in.	0.182	0.177
		mm	4.63	4.51
Unit load at failure or $0.8v_{peak}$		Kip/ft.	0.146	0.142
		KN/m	2.127	2.073
Drift at failure, $\Delta_{failure}$		in.	1.787	2.083
		mm	45.39	52.90
Shear modulus, G @ $0.4v_{peak}$		Kip/in.	3.276	3.254
		KN/mm	0.574	0.570
Work until failure per unit length		Kip-ft./ft.	0.022	0.025
		KN·m/m	0.097	0.113
Unit load, $v_{1/300}$ @ 0.32 in. (8.13 mm)		Kips/ft.	0.112	0.108
		KN/m	1.627	1.573
Unit load, $v_{1/200}$ @ 0.48 in.(12.19 mm)		Kips/ft.	0.133	0.134
		KN/m	1.941	1.950
Unit load, $v_{1/100}$ @ 0.96 in. (24.38 mm)		Kips/ft.	0.170	0.172
		KN/m	2.478	2.517
Unit load, $v_{1/60}$ @ 1.6 in. (40.64 mm)		Kips/ft.	0.174	0.171
		KN/m	2.540	2.501




Figure 04NA m 1r5- a. Observed and filtered load-deflection curves.




Figure 04NA m 1r5- b. Unit load-deflection and EEEP curves.




Figure 04NA_m1r5- c. Vertical displacement of studs.




Figure 04NA_m1r5- d. Sheathing displacement.